

Wolfe & Wiersema

Comparison of Various Floor
Systems in Reinforced Concrete

Architectural Engineering

B. S.

1913

THE UNIVERSITY
OF ILLINOIS
LIBRARY

1913
W832

The person charging this material is responsible for its return to the library from which it was withdrawn on or before the **Latest Date** stamped below.

Theft, mutilation, and underlining of books are reasons for disciplinary action and may result in dismissal from the University.

UNIVERSITY OF ILLINOIS LIBRARY AT URBANA-CHAMPAIGN

BUILDING USE ONLY

MAR 11 1979

MAR 11 1979

L161—O.1096

**COMPARISON OF VARIOUS FLOOR
SYSTEMS IN REINFORCED CONCRETE**

BY

**WILLIAM SIDNEY WOLFE
HARRY ANTHONY WIERSEMA**

THESIS

FOR

DEGREE OF BACHELOR OF SCIENCE

IN

ARCHITECTURAL ENGINEERING

COLLEGE OF ENGINEERING

UNIVERSITY OF ILLINOIS

1913

1913
W832

UNIVERSITY OF ILLINOIS

May 31

1913

THIS IS TO CERTIFY THAT THE THESIS PREPARED UNDER MY SUPERVISION BY

William Sidney Wolfe and Harry Anthony Wiersema

ENTITLED Comparison of Various Floor Systems in

Reinforced Concrete

IS APPROVED BY ME AS FULFILLING THIS PART OF THE REQUIREMENTS FOR THE

DEGREE OF Bachelor of Science in Architectural Engineering

Chas. R. Clark.

Instructor in Charge

APPROVED:

Fredrick W. Mann


HEAD OF DEPARTMENT OF

Architecture



Contents

	Page
I. Introduction.	1
1. Purpose and Methods.	1
2. Manufacturers and Contractors Literature.	3
3. Bibliography.	5
II. Girderless Floors.	6
1. Akme System	6
2. Cantilever Flat Slabs	8
3. Corr-Plate	9
4. Spider Web System	10
5. Turner Cantilever Flat Slab	10
III. Floors with Concrete Beams and Girders.	13
- 1. Bertine	13
2. Chaudy	14
3. Coignet	15
4. De Valliere	15
5. Gabriel	15
6. Hennebique	16
7. Kahn	17
8. Merrick	18
9. System M	19
10. Wilson	20
IV. Floors with Steel Beams and Concrete Slabs	21
1. Columbian	22
2. Matrai	22
3. Metropolitan	23
4. Roebling	23
5. White	24



Digitized by the Internet Archive
in 2014

<http://archive.org/details/comparisonofvari00wolf>

	Page
V. Arch Construction	26
1. Golding	26
2. Roebling Arch	27
3. Rolled Section Arches,--Melan, Monier, Wuench.	27
VI. Sectional Systems	29
1. Siegwart Beams	30
2. Unit	30
3. Vaughan	31
4. Visintini	32
VII. Combination Tile Systems	34
1. Corr Tile	35
2. Fawcett Tile	36
3. Kahn Tile	36
4. Johnson Tile	37
5. Nolan Tile	37
VIII. Plates Used Without Centering	38
IX. Systems with Fabric Reinforcement	40
X. Unit Frames	44
XI. Special Forms of Bars	45
XII. Design of Ten Typical Floor Panels and Conclusions	46
1. Procedure	46
2. Results	47
3. Conclusions	48

Index to Illustrations and Tables

	Plate	Page
Akme System	I	50
Akme System	II	51
Bertine System	VII	56
Cantilever Flat Slab System	III	52
Chaudy System	VIII	57
Concrete Steel Co. System	XV	64
Comparative Table	LVI	105
Columbian System	XVII	66
Corr Tile Floor Systems	XXVIII	77
Corr Tile Floor Systems	XXIX	78
Corr Plate System	IV	53
De Valliere System	X	59
Deformed Bars	XLI	92
Deformed Bars	XLIV	93
Deformed Bars	XLV	94
Design of Arch With Self Cen- tering Plate	LIV	103
Design of Corr Two Way Tile	L	99
Design of Expanded Metal Flat Slab	XLIX	98
Design of Hennebique System	XLVI	95
Design of Kahn Floredome Con- struction	LII	101
Design of Kahn One Way Tile	LIII	102
Design of Roebling System	LV	104

	Plate	Page
Design of Rib Trus Self Center- ing Plate	XLVII	96
Design of Turner Flat Slab	LI	100
Design of Vaughan System	XLVIII	97
Fawcett System	XXX	79
Fabric Reinforcement	XLI	90
Gabriel System	XI	60
Golding Ribbed Floor Arch	XXII	71
Graph Showing Variation of Cost with Load	LVII	106
Graph Showing Variation of Cost with Span	LVIII	107
Graph Showing Variation of Dead Load With Load	LIX	108
Graph Showing Variation of Dead Load with Span	LX	109
Hennebique System	XII	61
Johnson System	XXXII	81
Kahn System Floredome & Floretyle	XIII	62
Kahn System One Way Tile	XXXI	80
Matrai System	XVIII	67
Merrick System	XIV	63
Metropolitan System	XIX	68
Nolan Two Way Tile System	XXXIII	82
Roebbling System	XX	69
Self Supporting Metal Fabric	XXXVI	85
Self Supporting Metal Fabric	XXXVII	86

	Plate	Page
Siegwart Beam System	XXIV	73
Slabs Constructed Without Centering	XXXIV	83
Slabs Constructed Without Centering	XXXV	84
Slabs With Fabric Reinforcement	XXXVIII	87
Slabs With Fabric Reinforcement	XXXIX	88
Spider Web System	V	54
Systems With Arches and Rolled		
Sections	XXIII	72
Turner Cantilever System	VI	55
Types of Beam Reinforcement	LX	58
Types of Mesh Reinforcement	XL	89
Unit Bilt System	XXV	74
Unit Frames	XLII	91
Vaughan System	XXVI	75
Visintini System	XXVII	76
White System	XXI	70
Wilson System	XVI	65

Comparison of Various Floor Systems in Reinforced Concrete

I. Introduction.

1. Purpose and Methods.

In recent years a large number of different systems of reinforced concrete floor construction have sprung up in this country, some of which have attained wide commercial use. Information concerning these various systems is, however, scattered and inadequate. Many of the systems differ from each other only in the type of reinforcement which they employ; others in the method of placing the reinforcement; while some employ entirely distinct methods of construction. It is the purpose of this thesis to present information concerning all of these systems in such a manner as to give an adequate basis for comparison and classification.

In this investigation the important points concerning each system are arranged in the following order.

1. Commercial Use
2. Patents and Manufacturers
3. Loads, Spans, and Materials
4. Reinforcement
5. Design
6. Centering
7. Examples of Buildings
8. Tests and Failures

Letters were sent to all the manufacturers and contractors advertising in the more important engineering periodicals, and

the literature received in reply was investigated. On the next page is given a list of the companies whose literature was reviewed.

2. Manufacturers and Contractors

From Whom Literature was Received.

1. American Concrete Steel Co. -- Newark, N. J.
2. American Steel and Wire Co. -- Chicago.
3. American System of Reinforcing. -- Chicago.
4. Baltimore Siegwart Beam Co. -- Baltimore.
5. Barton Spider Web Company -- Chicago.
6. Berger Manufacturing Co. -- Canton, Ohio.
7. Brown Hoisting Machinery Company -- Chicago.
8. Clinton Wire Cloth Company -- Clinton, Mass.
9. Concrete Steel Company -- New York.
10. Concrete Steel Products Company -- Chicago.
11. Consolidated Expanded Metal Co. -- Pittsburg.
12. Corrugated Bar Company -- Buffalo.
13. General Fireproofing Company -- Youngstown, Ohio.
14. Hennebique Construction Company -- New York.
15. Interstate Iron and Steel Co. -- Chicago.
16. International Fence and Fireproofing Co. -- Columbus.
17. Jones and Laughlin -- Pittsburg.
18. National Fireproofing Company -- Chicago.
19. Nolan, J. S. & Company -- Chicago.
20. Northwestern Expanded Metal Co. -- Chicago.
21. Pittsburg Steel Products Company -- Pittsburg.
22. Standard Concrete Steel Co.-- New York.
23. Trussed Concrete Steel Company -- Detroit.
24. Turner, C. A. P. -- Minneapolis.
25. Unit Construction Company -- St. Louis.

26. Vaughan Company -- Detroit.
27. White Construction Company -- New York.
28. Wight, W. N. and Company -- New York.
29. Wilson System of Construction-- Boston.

3. Bibliography

1. Adams and Mathews -- Reinforced Concrete Construction
2. Atlas Portland Cement Company -- Factory Construction
3. Beton -- Kalendar
4. Brayton Standards
5. Buel and Hill -- Reinforced Concrete
6. Colby -- Reinforced Concrete in Europe
7. Expanded Metal System
8. Freitag -- Architectural Engineering
9. Freitag -- Fireproofing of Steel Buildings
10. Handbuch für Beton Eisen Bau
11. Heidenreich -- Pocket Book for Reinforced Concrete
12. Kahn System Standards
13. Laverigne -- Etude des Divers Systimes de Construction en Ciment Arme'
14. Kidder -- Handbook
15. Kidder -- Masonry Construction
16. Marsh and Dunn -- Manual of Reinforced Concrete
17. Radford -- Cyclopedia of Construction
18. Reid -- Concrete and Reinforced Concrete Construction
19. Richey -- Ready Reference
20. Sutcliff -- Concrete--Nature and Uses
21. Taylor and Thompson -- Concrete
22. Trautwine -- Concrete
23. Turneaure and Mauer -- Reinforced Concrete
24. Turner -- Concrete Steel Construction
25. Twelvetrees -- Concrete Steel
26. Twelvetrees -- Concrete Steel Buildings.

II. Girderless Floors

Among the various types of floor systems in use today, the girderless floor offers the greatest possibilities. It consists primarily of a flat concrete slab resting directly on the column tops, all projecting beams and girders being eliminated, and the material thus saved being used to increase the thickness of the slab.

Many advantages are gained by this method, the more important being a reduction in story height, increase in lighting area, and simplicity of centering. It is also advantageous where a uniform flat ceiling is desired in special cases; and also in case of fire, as it allows full sweep to a stream of water along the ceiling. It is especially well adapted to large floor areas, as in factory buildings, and the contractors claim that it is more economical for heavy loads than for light ones.

The analysis of stresses in girderless floors has not yet been placed on a substantial basis. The analogy is not strong enough to warrant the use of the theory of the circular plate, nor can the slab be properly designed as a plain cantilever. It has been customary, therefore, to base all designs on actual tests. These show that failures generally occur directly around the column top, due to diagonal tension. Heavy reinforcement is therefore required over columns.

The systems considered here are the Akme, the Spider Web, the Cantilever Flat Slab, the Corr Plate, and the Turner system.

1. Akme System

Plate I & II.

Girderless floors may be divided into two classes, those having four way and those having two way reinforcement. The Akme System was the first of the two way class to be used in actual building construction; its distinctive feature is the reinforcement of a wide strip, a, (see Plates I & II) extending over and parallel to the rows of columns, so that they will act as wide flat beams; and the reinforcement of the small square, b, as a common slab. In some cases the portion b is made thinner than the rest of the slab, thus giving a panel effect, and making the beam construction more apparent.

This system was patented by Mr. Condron of Chicago about 1908, and a royalty is retained for its use.

Spans used in this system vary from 14 x 14 ft. to 24 x 24 ft. and are designed for loads of from 100# to 225# per sq. ft., which loads they have successfully withstood with slight deflection in several tests.

As a rule some type of deformed or corrugated bars are used, which are bent up to the top of the slab, over the column, in order to take up the negative bending moment. The engineers of the company design this floor according to their own formula, giving dimensions of reinforcement for various spans and loads. It is seen that this system can be analyzed as four wide beams over the columns, supporting a central slab.

Ordinary wood centering is used except for the capitals, for which sheet metal forms are used. This system has been used in many buildings in the Central West, among which are the following: Wagner Electric Mfg. Co., St. Louis, Mo.; Warehouse of Peck and Hills Furniture Co., Chicago; Monogram Building, St. Louis, Mo.; and the Studebaker Automobile Co. Building, Chicago.

The following table of tests is given by the company.

Building	Column Spacing	Diagonal Span	Slab Thickness			Live-load #	Test Load			
			Max.	Min.	Ave.		#/sq'	Area sq'	Total load	Max. dif."
Stude-baker	24'-0"x 23'-9"	33'9"	12 "	6 "	8.6"	100	300	570	171000	0.34
Peck & Hills	14'-8"x 14'-0"	20'3"	7.5"	4 "	5.7"	150	280	196	54800	.06
Oak Pk. W H	16'-10"x 15'-3"	22'8"	9 "	5.5	6.5"	150	300	256	76800	.08
Peck & Hills	16'-2"x 15'-10"	22'7"	7.5"	4 "	5.5"	100	275	256	70400	.12
Sharples	18'-0"x 17'-5"	25'0"	8 "	8 "	8. "	225	550	625	34400	.22

2. Cantilever Flat Slab

Plate III.

This system is of the four way reinforcement class, and is similar in many respects to the pioneer system of this class, the Mushroom system, differing from it mainly in the reinforcing over and between the column top and the slab. This may be readily seen by reference to Plates III and VI. It is extensively used throughout the West and Middle West.

It is patented by the Concrete Steel Products Company of Chicago, the first patents being issued in 1902.

It is adapted to long spans, and loads varying from 100 to 200 pounds per sq. ft.

For reinforcement, plain bars are used, bent over the columns as shown in the illustrations.

The company furnishes details of design for particular buildings, basing the design upon actual tests, and no definite analysis of stresses has been given.

Wood centering with sheet metal capital forms is used.

Some of the more important buildings in which this system was used are as follows:

Rike-Kumber & Co. Department Store -- Dayton, Ohio.

Deere and Company Building -- Spokane, Wash.

Sickles and Co's Warehouse -- Davenport, Iowa.

Heath and Milligan Building -- Chicago.

Deere and Webber Building -- Minneapolis.

The company reports a test on the Quaker Oats Co. Building in Cedar Rapids, Iowa, in which six panels, 20' x 20' of a 9" slab were loaded with 315[#] per sq. ft., superimposed load, in which it is claimed there was no deflection.

Although tests have been conducted in which the stresses in the concrete and steel in different parts of the slab were measured, it is very doubtful if a rational basis for design can be deduced from the results. It is probable, however, that the floors as designed possess ample strength.

3. Corr Plate System

Plate LV.

This system is one of the newer forms of flat slab construction, using a two way reinforcement. As yet it has been used only to a limited extent. It was invented by the Corrugated Bar Co. of Buffalo, N. Y., and patent rights are reserved.

Spans from 15 to 25 feet, with a minimum thickness of from 5 to 14 inches and a live load of from 40 to 500 # per sq. ft. are recommended.

The reinforcement consists of corrugated bars placed as



shown in plate IV. No special form of reinforcement is used over the columns, but the bars are spaced closer. In designs furnished by the company, the allowable stresses are 18,000 # per sq. in. in the steel, and 750 # per sq. in. in the concrete.

The addition to the Ford Manufacturing Plant of the Ford Motor Co., of Detroit, Mich., was erected in this system.

4. Spider Web System

Plate V.

This system is another of the recent offshoots of the Mushroom System, using four way reinforcement, but differing from it in the reinforcement over columns. A fabricated mat of steel rods is placed over the column, as shown in Plate V. As yet it has been used but little commercially.

The inventors and promoters are the Barton Spider Web System Company of Chicago, and patents are now pending.

It is presumed that this system can be used for long spans and heavy loads, similar to other flat slab systems, although as yet experimental data is limited.

From the illustration it appears that especial attention has been given to the reinforcement for stresses over the columns. As usual, the company furnishes designs.

5. Turner Mushroom System.

Plate VI.

As has been stated, the Mushroom system was the first of all girderless floors. It has been widely used throughout the Middle

West, but has not found much favor in Chicago, on account of the strictness of the building ordinances there. It uses four way slab reinforcement, and is especially well reinforced over column tops, as may be seen by reference to plate VI.

This system was invented and patented by Mr. C. A. P. Turner of Minneapolis, about 1905. Many of the later girderless systems are considered infringements of the patent, and have been vigorously prosecuted.

The floors have been used with spans from 16 to 30 feet, and for loads from 100 to 500 pounds per square foot. They are not economical for light loads, and hence are used chiefly in factory buildings and warehouses.

Plain round bars are used for reinforcement, as the engineer is strongly opposed to deformed bars of any kind. The method of placing the bars is easily understood from Plate VI. The flaring capital, with the heavy bars extending into the column and bent out radially into the slab, combined with the circumferential reinforcement, provides amply for shear over the column, which is the most dangerous section.

In the design of the slab, a bending moment of $1/50 WL$ is used. The constant $1/50$ was obtained by measuring the stress in the steel for a certain load in an actual test, and solving from the equation

$$KWL = A_s .85 d f_s$$

Knowing the load W , the span L , the area of the steel A_s , the depth d , and the stress in the steel f_s , the constant K was determined as $1/50$. This is a very small value for the moment, as most building ordinances require that all floors shall be designed for a moment of $1/25 WL$

at the center. The engineer computes that for a moment of $1/50 W L$ the deflection should be $1/7000 \frac{W L^3}{A_s d^2}$, and he claims that in many tests the measured deflections have borne out the accuracy of this formula.

As in all girderless systems, the centering required is very simple.

Some of the buildings in which this system was used are as follows:

John Deere Plow Co. Building - Omaha

Bostwick - Braun Hardware House - Toledo, Ohio

T. & B. Moose Building - Chicago

Grellet Collins Building - Philadelphia

"Soo" Line Freight Station - St. Paul

Many other buildings have been erected in St. Paul and Minneapolis using this system. In many of the buildings tests were made and deflections observed, but no records are available of any tests to destruction.

III. Floors with Concrete Beams and Girders

The oldest types of reinforced concrete building construction use flat slabs supported between concrete beams, these in turn being supported on girders and columns of concrete. By far the greater number of reinforced concrete floors have been constructed in this way. The forms are all built of wood, and the concrete for one entire floor is poured at one time, thus producing a monolithic construction.

There is no difficulty in designing a floor of this nature, each member being designed to carry the load imposed on it, according to the ordinary reinforced concrete beam theory; the same procedure as with a wood floor construction. To place the reinforcement efficiently with a minimum of labor is the chief problem which has evolved; and many systems have been invented for its solution, especially in Europe, where more attention has been paid to reinforced concrete design. Many systems use only a different kind of reinforcing metal, while others use a distinct method of placing the reinforcement. The Hennebique System is perhaps the best known and oldest of all. The systems treated here are the Bertine, Chaudy, Columbian, Coignet, De Vallier, Gabriel, Hennebique, Kahn, Merrick, M System, and Wilson.

1. Bertine

Plate VII.

The Bertine system is typical of a great many systems of lesser importance, in which the floor slab is composed of a number of reinforced concrete tee-beams connected together. As a rule each

engineer designs his own system, and this particular type, or Bertine system, has never gained very great prominence.

Such floors can be used for spans of about 16 feet and develop considerable strength. The floor with dimensions as shown in plate VII. was designed for a load of 450 pounds.

The reinforcement consists of rods 1 inch in diameter, to take both tension and compression. The beam reinforcement for this system is rather distinctive, as shown, the stirrups being of 5/16" rods.

In this system, and in all similar systems, the tee-beams and supporting girders are designed according to the standard theory of reinforced concrete beam design, as given in all textbooks on the subject.

This system was used by Bertine and Son, Engineers, on the Bush Terminal Company Factory, at South Brooklyn, New York.

As each engineer will design his floors somewhat differently from every one else, and as the number of such designs is unlimited, no attempt will be made to consider all of such systems.

2. Chaudy System

Plate VIII.

This is a European system used chiefly in France, the main feature being double reinforced beams.

It was invented by Mr. Chaudy of Paris. The floors are designed as a series of T-beams connected to each other. The compressive and tensile reinforcement of the beam is connected by small rods which act as stirrups. The concrete in the beam is considered as

only a web connecting the reinforcing steel. See Plate VIII.

3. Coignet System

Plate IX.

This system is very similar to the previous one, the main difference being in the fabricating of the stirrup. This is shown in Plate IX, together with other systems using a similar form of reinforcement. In all these systems the compressive reinforcement is lighter than the tensile. The floor itself is designed as a series of connected T-beams. These systems are used to some extent in France.

4. De Valliere System

Plate X.

Another system differing only in the method of reinforcement is the De Valliere system, also originating in France. In this system no compressive reinforcement is used. The peculiar web reinforcement which is shown in Plate X is the distinguishing feature.

5. Gabriel System

Plate XI.

This is at present a rather unimportant system, sometimes considered as an offshoot of the Kahn System. It was designed by the Gabriel Reinforcement Co., and possesses several more or less distinctive features. The method of web reinforcement is shown in plate XI., also the beam connection to the column; woven wire is used for slab reinforcement. By increasing the depth of beams and girders

long distances may be spanned and heavy loads carried.

6. Hennebique System

Plate XII.

This system is one of the first successful systems of reinforced concrete construction. It is a monolithic construction of columns, girders, beams and slabs, with distinctive reinforcement, as shown in Plate XII. An arched slab is also sometimes used between beams.

This system was invented in France by Hennebique about 1885, and has been used extensively throughout Europe and lately in the United States, where it was patented in 1898. The patent rights are controlled by the Hennebique Construction Company, with its main office at New York City, and branch offices in many of the larger cities. It is claimed that over one hundred million dollars worth of work has been erected under the supervision of this company.

This system is well adapted to long spans, girders of 50 foot span being quite common. It is also adapted to heavy loads, ranging up to 200 pounds live load per square foot.

Round rods are generally used for reinforcement in slabs and beams, as shown in Plate XII, the ends being split and flared out to give a good grip. In this system some of the tensile reinforcement was first bent up near the end of the beams to provide for shear and negative bending moment. Shear is further provided for by vertical stirrups composed of flat bars bent around the tensile reinforcement in a U-shape and hooked at the top.

Ordinary flexure formulas for reinforced concrete may be used in the design of this system.

A few of the more important buildings constructed with this system are as follows:

William McKinley High School - St. Louis

United States Express Co. Stables - Jersey City, N. J.

Metropolitan Life Insurance Company - Bronxville, N. Y.

Princeton University Dormitories - Princeton, N. J.

Many tests have been performed on actual buildings and deflections measured, showing that the floors are entirely safe, but no tests to destruction with measurement of actual stresses have been reported.

7. Kahn System

Plate XIII.

The Trussed Concrete Steel Company of Detroit uses a type of construction very similar to the Hennebique, except for the use of their patent Kahn bar for reinforcement. This bar is well shown in Fig. 3, Plate XIII. This system has had considerable success in America, and the bars have been used to some extent in Europe.

In all other particulars, this construction is similar to the Hennebique system, and it may be designed in the same manner, except for the shear taken up by the projecting pins.

Floredome and Floretyle

Plate XIII.

This company also employs a construction using tile, (see Chapter VII) and one using hollow metal forms forming coffers on the under side, as shown in Plate XIII. This system is entirely

different from the preceding systems, as it divides the floor into a series of adjacent T-beams running either one or two ways as shown in Plate XIII. This system is comparatively new, and has not gained much prominence as yet.

It is not especially well adapted to heavy loads or long spans.

Kahn bars are used for reinforcing the T-beams, both the bars and the metal domes being supported on Hy-rib, which acts as partial self-centering, and may be plastered on the under side to form a flat ceiling.

Tables for design are furnished by the company, computed with ordinary theory for a bending moment of $1/10$ W L. Actual data from tests, however, is lacking.

Some of the more important buildings in which this type of construction has been used are: The Railway Exchange Building, St. Louis, Mo.; Packard Service Building, Los Angeles, Cal.; and the Mt. Tabor School, Portland, Ore.

8. Merrick System

Plate XIV.

This system is similar to the Kahn Floredome system previously described, using a hollow metal dome, similar to a tile system. By reference to the drawing, Plate XIV, it is seen that the floor is comprised of a number of beams laid adjoining, with a coverplate and an underneath plate of concrete.

The system has been used considerably in the East. Patent rights are held by Mr. E. Merrick of New York.

Spans 16 to 18 feet are used for loads of 75 # to 100 #. Dimensions for a 14 foot span are shown in the illustration.

The reinforcement consists of 3/16" rods laid as shown. The system is designed as a series of rectangular beams, the lower or ceiling slab of 2" being of cinder concrete, while the remainder is stone concrete.

Ordinary flat centering is required.

9. System M

Plate XV.

System M has been put on the market by The Standard Concrete Steel Company of New York City, and has been used to a considerable extent in the East. It is well adapted to long spans and heavy loads. Floor beams up to 50 feet in length have been used with success, and several buildings have been designed for floor loads of 250 # per square foot.

In this style of construction the tension reinforcement for the beams and girders is composed of rolled sections bolted or riveted to metal columns, (sometimes of cast iron) which form the column reinforcement. Stirrups are provided by passing rods through the web of the rolled sections and bending them up. Rods or metal fabric may be used for the slab reinforcement.

The common theories of design may be applied to this system. The steel skeleton is constructed ahead of the concrete and assists in supporting the centering.

Some of the important buildings constructed in this system are: The Maryland State Tobacco Warehouse; 102-4 Fifth Ave. Building,

New York City; Building at Grand and Mercer Sts.; New York City, and the United States Medical Stores, Greenwich, New York.

Very little information is obtainable regarding tests. A portion of the floor of the Maryland State Tobacco Warehouse, designed for 200 # per square foot, successfully withstood a load of 870 # per square foot with but slight deflection.

10. Wilson System

Plate XVI.

In this system the columns, beams, and girders are of reinforced concrete, while the floor proper is of plank. It has been developed from the ordinary mill or slow burning construction, differing from it in using reinforced concrete for the supporting members. This system was patented by the Wilson System Company of New York City in 1911, and has been used in a number of eastern buildings. It is well adapted to long spans and heavy loads.

The reinforcement is not a distinguishing feature, common bars with rod stirrups being used. The common beam and column theory is all that is necessary for design.

This system has been used in a number of buildings in Massachusetts among which are: The Stoughton Rubber Co., Stoughton, Mass.; Shoe Factory for Chas. W. Dean and Company, Motick, Mass.; and Printing Plant for T. Mong & Son, Greenfield, Mass.

IV. Floors with Steel Beams and Concrete Slabs

The increasing height of buildings in large cities has led to the development of a floor construction using a steel frame work, with a reinforced concrete slab between beams. This is because the heavy loads necessitate the use of concrete columns of such large diameters as to make their use prohibitive, while the difficulty of attaching concrete beams to steel columns makes advisable the use of steel for the beams and girders as well.

The steel frame work in this type of construction can be erected rapidly, and the concrete slabs put in later. In all the best types, the concrete is also placed around the beams and columns, thus forming a light, rigid, and fireproof building construction. This type has come to be used also in smaller buildings, on account of its lightness and ease of construction, combined with fire-proofness.

In order to secure a flat ceiling with this type, either a suspended ceiling must be used, or the slab placed lower and a cinder fill put in. Other items of expense are the complicated wood forms around the beams, and the placing of reinforcement, which have led to the development of stiff reinforcing plates, of combination tile systems, and of a built up fabric reinforcement. All of these departures will be treated in later chapters.

Unlike the previous type, in which most of the systems originated in Europe, the systems of this type are for the most part American. Those treated here are the Columbian, Kahn, Matrai, Metropolitan, Roebling and White.

1. Columbian System

Plate XVII.

The distinguishing feature of the Columbian system is the Columbian reinforcing bars and the methods of connecting them to the metal beams which are usually used as the supporting members; however, concrete beams reinforced with Columbian bars are sometimes used. Plate XVII shows the general appearance and a number of the details of this system. In the past this system has been used to some extent in the United States, but at present it is used very little.

It may be used with long spans and heavy loads and is easily designed. The reinforcing steel is a peculiar rolled section, drawings of which are shown in Plate XVII.

2. Matrai System

Plate XVIII.

This is a French system invented by M. Matrai, and used to some extent in France. It is really an inverted arch, as shown in Plate XVIII, in which the stress is taken up by tension wire cables forming a complicated network. The beams supporting the panel edges are sometimes constructed of reinforced concrete, using a reinforcement as shown in Fig. 3, Plate XVIII. Panels 25 x 12 feet have been used with success.

In designing this system it is assumed that the wire cables carry all of the stress, the concrete acting as a filler. These wires are attached as near the ends of the beam as possible, in order to reduce the moment. This system was used in the construction of

the Maison d' Education de la Legion d' Honneur.

3. Metropolitan System

Plate XIX.

This system was formerly known as the Manhattan, and is manufactured by the Metropolitan Fireproofing Company of Trenton, N. J. The reinforcement consists of twisted galvanized wires supported by beams as shown in Plate XIX. A $7/8$ in. round rod is placed in the center of the span and parallel to the beams, to bring the wires to a uniform deflection. The use of this system is not extensive at the present time.

4. Roebling System

Plate XX.

The Roebling System is one of the standard systems for use with steel beams. Its distinctive feature is reinforcement of flat bars set on edge and spaced with separators. It has had wide commercial success in all parts of the country; in New York, Chicago, in the West and in Canada.

The system was invented by John A. Roebling, the designer of the Brooklyn Bridge, and patent rights are held by the Roebling Construction Company with their main office at New York City.

The maximum span used is 16 feet, although it is more economical to use smaller spans. The loads supported are fairly large, 150 pounds being usual. Cinder concrete is often used, a 1-2-5 mixture being common.

The reinforcement consists of either 2" x 1/8" bars 16" on centers or 3" x 1/4" bars 12" on centers. The bars are set on edge and held upright by separators spaced about 2 1/2 feet, and made of No. 5 rounds bent over the flat edge of the bar. The ends of the bars are fastened to the steel beams in various ways, as shown in Plate XX, or may be simply laid over the beams.

Slabs may be designed in the ordinary way, but it is customary to require a deflection test before accepting work.

The centering required, as in all similar systems, is quite complicated, on account of the beam fireproofing. The beams are usually wrapped with wire, or clips are used to tie the concrete to the beams.

In the past this system has been used in a great many buildings, although its popularity is on the wane.

Tests have been mostly of deflections.

Costs given by Mc Arthur for 1910 are as follows:

	per sq.ft.	span	depth of beams
Flat, with Ceiling	20¢	7'	10"
" without "	17¢	7'	10"
4" Slab	14¢	4'	4"

5. White System

Plate XXI.

By reference to Plate XXI, it is seen that the White System is very similar to the Roebling system, except that round bars are used for reinforcement instead of flat bars. This system is used extensively throughout the East, especially in New York.

It was patented about 1903, the rights being held by the White Fireproofing Company of New York City.

The loads range from 100 to 200 pounds for spans of between 6 and 8 feet. For beams 8'-0" on centers a 4" slab is used, of 1-2-5 cinder concrete, weighing 59 #/sq.ft.

The reinforcement consists of 9/16" round rods 9" on centers, fastened to the steel beams in different ways, as shown in the illustration.

These slabs can be designed in the usual manner, but in cities the loads allowed are generally based on tests rather than on design.

A few of the buildings using this system are:

Germania Life Building - New York

Union Theological Seminary - New York

Globe Theater - New York

Hotel Kimball - Springfield, Mass.

Confederation Life Building - Toronto

The system was tested officially by the New York Building Department, and the slab carried a load of 600 pounds per square foot easily after the completion of a fire and water test of four hours.

V. Arch Construction

The arch construction represents the most economical type of floor as far as economical disposition of material is concerned, but the great cost of curved wooden forms is a serious drawback to its use. In fact, except with small spans where a mesh or plate can be sprung between supports, the cost of centering almost prohibits the use of arched concrete floors.

While there is no accurate theory to determine the strength of such floors, the strength actually developed by these arches, as shown by numerous tests, is very remarkable. Arches only two or three inches thick at the crown will sustain loads of 500 to 1000 pounds per square foot. Provision must always be made to take up the thrust of these arches, and while little steel reinforcing is needed in the arch itself, the amount used in tie rods to take up the thrust is almost equal to the amount needed in a flat slab of the same span.

Almost all systems which employ flexible reinforcement can be used in arch construction, and will develop greater strength in this manner; but the economy is usually slight. The difficulty in securing a presentable ceiling, which cannot be done without suspending a separate flat ceiling, is also a drawback to its use.

1. Golding Ribbed Arch

Plate XXII.

This arch is plainly shown in the illustration, Plate XXII. It was invented by Golding, the inventor of the first expanded metal.

The reinforcement consists of expanded metal, while the arched ribs are used for stiffening. This provides an effective use of material, but the ultimate economy of the system is doubtful.

2. Roebling Arch

A Roebling floor arch is shown in Fig. 6, Plate XX. This was one of the first arch systems to be used, and is typical of all the systems using fabric reinforcement, but in recent years it has practically gone out of use. It is controlled by the same company as that controlling the Roebling flat arch.

It is claimed that very heavy loads can be supported by these arches, based on results of actual tests, as all theories of design are inaccurate. Cinder concrete is generally used.

The reinforcement consists of wire lath with 3/16" rods interlaced, 9" on centers. This stiffens the lath so that it can be sprung between beams, and the concrete poured in without the use of centering.

3. Rolled Section Arch

Plate XXIII.

In Europe rolled sections are used to reinforce floor arches. Three of the more common arch systems, the Monier, the Melan, and the Wuench, are shown in Plate XXIII. It is easily seen that enormous strength can be developed in this way with light slabs, but the expense of curving the rolled sections is too great to allow of its use except in special cases. In bridge floors their use is common.

The sections used are angles or tees, and these are curved to give a rise of about $1/20$ of the span.

VI. Sectional Systems

Sectional systems of reinforced concrete floors differ from all other systems in that members of reinforced concrete are cast in moulds, and after drying are carried to the building site and set in place, the same as wooden joists.

In this way all centering is eliminated. The members can be reinforced and poured under close supervision, and a uniform product is assured. They can be built under cover and allowed to harden any required length of time, so that building work can proceed in all kinds of weather. On the other hand, a structure of this nature has not quite the same rigidity as a monolithic structure.

In all concrete work, the labor item is by far the most important item of cost, and centering causes the largest part of the labor cost. As these systems require no centering, and as factory labor is far cheaper than field labor, these systems should present a considerable reduction in cost; in fact, this is the greatest argument in their favor. In Europe, where these systems originated, this has indeed proved true, but in this country the scattered cities and the high railroad rates have so increased the transportation costs as to offset any gain. Then, too, the use of ready built members is scarcely feasible where many floor openings are required; it is only in straight work that it can be used with any degree of success.

For these reasons these systems have not met the same success in America that they have in Europe. Several systems have been withdrawn from the market, including the "Hollow Concrete I Arch System", and none have gained very extensive commercial use. Those

considered here will be the Siegwart Beam, the Unit System, the Vaughan, and the Visintini System.

1. Siegwart Beam System

Plate XXIV.

As yet this system has not been used to any great extent in this country, although its use is rapidly increasing. In Europe the manufacture of Siegwart Beams is carried on in about 40 different cities, and over 40,000 sq. yds. are turned out per year. Only one factory is located in the United States.

The system is patented. It consists of flat hollow reinforced beams, which may be supported at their ends by rolled steel sections, as shown in Plate XXIV. The top is a little narrower than the bottom, and the sides have small grooves; the space thus formed is filled with grout, cementing the beams together.

This floor may be designed for heavy loads, and may be used for reasonably long spans. The reinforcement is simple, consisting of rods and stirrups, and the theory is that of simple reinforced concrete beams.

The cost of this system is reasonably low, except when the freight charges are excessive.

2. Unit Bilt System

Plate XXV.

The Unit Bilt System differs from the Siegwart Beam System in many ways. In the Unit Bilt System columns, girders, beams, wall

slabs, floor slabs, and roof slabs are all cast in the factory and sent to the job as units; moreover, these units are all solid. At the joint the reinforcing is allowed to project beyond the units, and the joint is poured with grout, thus cementing the members together. This method of construction is patented in the United States and in foreign countries. The general offices of the company are located at St. Louis, Mo.

The reinforcement is not a distinguishing feature, and common rods may be used.

As with other unit systems, one of the strongest points in its favor is the fact that no centering is needed.

3. Vaughan System

Plate XXVI.

This system is similar to the Siegart Beam System, the main difference being in the section of the beam and in the form of stirrup. The section of these beams is roughly an I beam, as shown in Plate XXVI. The makers of this product are the Vaughan Company of Chicago. Patents have been applied for.

The reinforcement is simple, consisting of rods in the lower portion and a peculiar form of stirrup, as shown in Fig. 3, Plate XXVI.

The company gives a table of dimensions for spans up to 25' and loads up to 250 # per square foot, using the stress in the steel as 16,000 # per square inch, the stress in the concrete as 750 # per square inch, and $M = 1/8 wl^2$.

A beam was tested by the company, in which it is claimed

that the stress in the steel reached 50357 # per sq. in.

4. Visintini System

Plate XXVII.

This is one of the oldest of the sectional systems, and one which has had the widest use, especially in Europe. As seen in Plate XXVII, it consists of beams of concrete, cored out and cast so as to form latticed girders. These beams are set side by side, to form a flat floor and ceiling.

Franz Visintini of Zurich, Switzerland invented the system, which was introduced in America for the first time by the Concrete Steel Engineering Company of New York in 1905.

The floors are very light, as can be easily seen, since the beams are only 6 to 12 inches wide and 6 to 8 inches deep. It is therefore best adapted to light loads, but long spans can be used up to 30 or 40 feet.

The top reinforcement is 1/4" round and the bottom 3/8" round, while the diagonal reinforcement is 1" x 1/8" straps, with holes punched, through which the top and bottom reinforcement is threaded.

These beams form a truss construction, the beams, Fig. 1, being Warren trusses, and the girders, Fig. 4, being Pratt trusses. Thus the stresses in the members can be fairly accurately determined by the method of truss analysis, a diagram for which is shown in Fig. 5. Thus the members can be designed to carry the exact stress in tension or compression. Fig. 2 shows the method of anchoring the beams to the wall, and Fig. 3 shows the method of lifting them

with a rope and an iron frame which fits over the end.

This system was used in a factory for the Textile Machine Works of Reading, Pennsylvania.

VII. Combination Tile Systems

Another new form of construction which aims at economy is the combination tile and reinforced concrete system. Many attempts have been made to save the concrete in the lower part of the slab which is not used for tension or compression, by forming T-beams, placing the greater part of the concrete near the top of the slab, where it can be used for compression. The great cost of forms for this beam construction, however, generally more than offsets the saving in concrete. The combination tile systems, however, place a tile in the lower part of the slab, thus displacing part of the concrete without necessitating complicated forms.

Some of the best systems have eliminated the complicated centering still further by allowing the edge of the tile to rest directly on a plank, while the concrete is poured in the spaces, thus requiring only half of the area to be centered. In this way an economical floor is provided, consisting of a series of T-beams, while plaster may be applied directly to the underside of the tile and concrete, forming a flat ceiling.

This system has the added advantage of being very light, and where tile can be obtained cheaply, is certainly very economical, while allowing fairly long spans and heavy loads.

Forms of tile differ somewhat, and one-way and two-way reinforcement is used. In Europe there are a great many special shaped tile in common use, such as circular and part circular. Some of these are devised to carry pipes and wiring, thus concealing and fireproofing them.

These systems are similar to the steel Floredome and Flore-tyle system described in Chapter III, except that tile is used instead of the metal boxes.

The systems treated here are the Corr Tile, Fawcett, Kahn, Johnson, and Nolan Tile Systems.

1. Corr Tile Floor System

Plates XXVIII & XXIX.

The Corrugated Bar Company is the promoter of several systems of reinforced concrete floors, among which are three forms of two way tile construction. These three forms or systems differ only in the shape of tile used and in the way of setting them so as to close the holes at their ends.

In their handbook, the Company gives tables of thickness and loads for spans up to 30 x 38 feet. Corrugated bars are used for reinforcement. In designing this system, the company uses as a basis for their formulae and computations, $M = \frac{1}{32} w l^2$, on square panels. This value is used for both positive and negative moments in fixed panels.

In this type of construction, the amount of centering is somewhat reduced, the tile answering the purpose in part.

In 1911 a panel of one of these floors designed for 150 # was tested up to 650# per square foot without reaching the yield point of the steel or producing excessive deflections.

2. Fawcett System

Plate XXX.

Strictly speaking, this is not a system of reinforced concrete for the steel beams really carry most of the load, while the concrete acts more as a filler above the tile. As shown in Plate XXX it consists of rolled beams supporting terra cotta lintels, which in turn support the concrete floor. It seems to be little used at the present time.

3. Kahn System One Way Tile

Plate XXXI.

This form of construction is like Corr Tile Floors in many respects, but it differs in one important feature in that the reinforcing is placed in only one direction. This permits the tile to be placed end to end and avoids the necessity of having a tile plate to stop up the holes. This system is a product of the Trussed Concrete Steel Company of Detroit. The company also has offices in London and Toronto.

The reinforcement is the Kahn Trussed Bar (see Fig. 3, Plate XIII). Plate XXXI shows the appearance of these bars in the floor. In their booklet "Kahn System Standards" the company gives several tables of safe loads for spans varying from 8 to 29 feet and thicknesses varying from 8 to 15 inches including tile and concrete. These tables are based on a bending moment of $1/10 w l^2$, and from trial the allowable stresses are found to be 500 and 16000 in the concrete and steel respectively.

4. Johnson System

Plate XXXII.

This is a one way tile system patented by the National Fireproofing Company of Chicago. The general method of construction is shown in Plate XXXII.

It is seen that this system is similar to the others, but does not possess the advantage of dispensing with centering. Also in type 1 there is no concrete in compression, which would seem inefficient. Hence a design as a concrete beam will not be satisfactory.

5. Nolan Two Way Tile

Plate XXXIII.

The promoter of this system is J. S. Nolan and Company of Chicago. Both United States and foreign patents have either been granted or are pending. It has been used in various structures through the Central West, several of which are in Chicago. This system is very similar to Corr Tile Floors, differing from them only in minor details. Long spans and reasonably heavy loads may be used. However, it is best adapted to light loads and comparatively long spans. The design is that of a flat slab supported on four sides, thus making the computation of stresses somewhat difficult and uncertain. Havemeyer bars are used for reinforcement. No stirrups are used but the bars are bent up at the end.

The new West Side Y. M. C. A. of Chicago was constructed with floors of this system.

VIII. Plates Used Without Centering

Plates XXXIV to XXXVII.

Besides the sectional systems and the tile systems, a third system aiming at the reduction of the cost of centering makes use of self-centering plates. These are simply metal plates which are stiff enough to carry a concrete slab with but slight bracing. The plates are laid across steel or concrete beams in a number of different ways as shown in Plates XXXIV and XXXV, and concrete is placed on top, while the under side is plastered with cement plaster. The plate, being thus fireproofed, serves as reinforcement for the slab.

The plates may be supported in various ways, and may be arched if desired as shown in the illustrations. There are a number of companies which manufacture these plates, many of them being very similar, as shown in Plates XXXVI and XXXVII. The more important types are shown and are as follows:

Fig. 1, Rib Truss -- Berger Mfg. Company

" 2, Multiplex Steel Plate -- Berger Mfg. Company

" 3, Ferrolithic Plate -- Berger Mfg. Company

" 4, Self-centering -- General Fireproofing Company

" 5, Hyrib -- Trussed Concrete Steel Company

" 6, Corr Mesh -- Corrugated Bar Company

" 7, Ferroinclave -- Brown Hoisting Machinery Company

" 8, shows the various methods in which these plates may be obtained bent to shape.

These various forms of metal plates have been patented, but have not had a very wide commercial use as yet.

The spans are necessarily short varying from 3 to 10 feet between beams. Loads up to 200 # can be carried, with which the slab weighs about 60 # per square foot. The thickness of the slabs vary from 1 1/2 to 3 1/2 inches. For the longer spans the plates must be supported in two or three places.

The reinforcing plates generally come about 28 inches wide and 4 to 12 feet long. In those fabrics having raised ribs, the ribs are about 13/16 inches high and about 3 1/2 inches on centers. The area of the steel may be found from tables and may be verified by measurement. The following is given for Self-centering:

Gage	Sectional Area - sq.in.
28	.177
26	.213
24	.284

From this area and the dimensions of the slab, the safe load can easily be computed. In tables furnished by the same company, a stress in the steel of 16,000 and in the concrete of 800 pounds was assumed. It is somewhat questionable, however, if the entire sectional area can be considered effective in withstanding the moment, for the coat of cement plaster can scarcely be considered efficient fireproofing.

The elimination of centering is, of course, the principal advantage of this system. It is very well adapted to roof construction.

The Oil House of the Rumley Company, La Porte, Indiana, and the Ohio State Reformatory at Mansfield, Ohio, are examples of buildings with this type of floor.

IX. Systems with Fabric Reinforcement

Plates XXXVIII to XLI.

In order to reduce cost by simplifying the process of laying reinforcement, a great many forms of fabricated metal have been devised. As a rule this fabric is used with a construction employing steel beams, although it can also be used with concrete beams. The fabric may be supported in many different ways as shown in Plates XXXVIII and XXXIX.

Some of the heavier types are shown in Plate XL, the Hyatt, Donath, and Muller being flat bars on edge connected with cross bars to space them evenly, and the Chaudy being a row of round bars with a thin plate interwoven. These types are used principally in Europe and have not very wide-spread use.

Plate XLI illustrates some of the lighter types. Figure 1 illustrates Steelcrete Expanded Metal Lath, perhaps the best known and most widely used of all. It is made out of sheets of steel, split cold and pulled out to 3 to 8 times its original size. The sheets come in sizes of 12 to 72 inches in width and 8 feet in length. The thickness of plate varies from # 27 to # 3 gauge, and the size of the mesh from $3/8$ " to a 5" x 12". This metal was invented by Mr. Golding in 1890, and its manufacture in America is now in the hands of the Consolidated Expanded Metal Lath Companies, which is a consolidation of separate companies under different names in Chicago, Pittsburg, Boston, New York, Philadelphia, St. Louis, Washington, Buffalo, San Francisco, and Toronto.

The sectional area of this expanded metal may be obtained from tables.

Figure 2 illustrates Clinton Welded Wire, invented in 1840 and manufactured by the Clinton Wire Cloth Co. of Clinton, Massachusetts. The rectangular mesh varies from 3 by 8 to 8 by 10 inches, and is electrically welded at intersections. The carrying wires are #10 to #4, and the distributing wires #11 to #6. The mesh comes in 60 inch rolls.

Figure 3 shows Cottancin wire, a fabric used chiefly in Europe.

Figure 4 is Lockwoven Steel Fabric, manufactured by W. N. Wight and Company of New York. This has been extensively used for reinforcement during the last ten years. The longitudinal wires vary from #14 to #7, and the cross wires are #14, the mesh being 3 x 12 or 1 1/2 by 12 inches. The sheets are 54 inches wide.

Tie Locked Fabric, Figure 5, is a similar mesh using the peculiar shaped tie shown and manufactured by the International Fence and Fireproofing Company of Columbus, Ohio. This comes in sheets 45 to 60 inches wide and any length. The mesh is 4 by 6 inches, the wires #18 to #6 gauge. This company supports the fabric on wire cables for long spans.

A triangular mesh, Figure 6, has been used by the American System of Reinforcement, Chicago, since 1887. The wires are #7 and #11 gauge, the mesh 4 inches. This fabric has had wide use.

Rib Metal, Figure 7, manufactured by the Trussed Concrete Steel Company of Detroit, is a comparatively new product in which the cross members are formed from the same sheet of steel.

This type is best adapted to light loads, 75 # to 150 #, and short spans, 6 to 15 feet. Where the fabric is galvanized, cinder concrete may be used, giving a light dead load.

The sectional area is obtainable for all the various types of reinforcement shown, and the slab may be designed by the ordinary beam theory. Tests show that for short spans such slabs develop considerably greater strength than the design attributes to them, due to arch action in the slab, but this quantity is uncertain and it is best to rely on the usual theory for design.

Ordinary centering is required. The fireproofing of beams should not be carelessly done as is so often the case with this type.

The advantage of a fabricated mesh is economy in laying reinforcement and assurance of correct spacing. Moreover, the fabric can easily be bent to the top of the slab over beams to provide for negative bending moment.

Any number of buildings have been constructed with the use of some of these forms of reinforcement, and many tests have been performed. Below are the results of some tests on expanded metal slabs, it being the most widely used.

Tests on Expanded Metal Floors

No.	Where Made	Kind of con- crete	Span ft.	Load per sq ft lbs.	Center Load lbs.	Deflec- tion at center in.	Reinforced with ex- panded met- al
1	N.Y.Sugar Refin- ing Co., Long Is- land City, L.I.	Cinder	4	--	40,000	0	3"-No.10
2	N.Y.Sugar Refin- ing Co., Long Is- land City, L.I.	"	4-10	--	37,000	3/8	3"-No.10
3	Larkin Soap Fac- tory, Buffalo, N.Y.	"	4	2333		5/8	3"-No.10
4	Y.M.C.A Building, Buffalo, N. Y.	Cinder & Stone	17-8	800		0	3"-No.10 rods 16" c-c
5	Edison Power House, New York, N. Y.	Cinder	5		122500	Arch	3"-No.10
6	Gov't Hospital for Insane, Wash- ington, D. C.	"	6	1256		3/16	3"-No.10
7	Merchants Refrig- erating Co., Jer- sey City, N. J.	"	7	2400		5/16	3"-No.10
8	Board of Harbor Commissioners, San- Francisco, Cal	Stone	7	750		0	2 1/2"-No.16
9	Columbia Univer- sity, New York, N. Y.	"	15	600		5/8	6"-No.4 1/2" rods

X. Unit Frames

Plate XLII

Besides fabric reinforcement for slabs, several attempts have been made to secure a unit reinforcement for beams, to accomplish the same purpose, and from which unit frames have evolved. Plate XLII illustrates three of these.

Figure 1 is a frame manufactured by the American System of Reinforcement, Chicago. The tensile and shear reinforcement are rigidly attached to each other and the frames can be ordered to size ready to put into place.

Figure 2 is a frame manufactured by the Corrugated Bar Company of Buffalo, New York. The stirrups are pivoted to the longitudinal reinforcement of corrugated bars so as to produce a collapsible frame, facilitating shipment. The General Fireproofing Company of Youngstown manufacture a similar pin connected frame.

Figure 3 is a frame manufactured by the Pittsburgh Steel Products Company, which was originally known as the Cummings Frame. The stirrups are placed at 45 degrees, made of $1/8$ " strips, $1\ 1/2$ " wide, electrically welded to the longitudinal bars.

All of these frames decrease the labor cost of setting reinforcement, and insure its proper position in the beam. Where the factory is easy of access and the shipping costs not too large, their use should result in a considerable saving.

XI. Deformed Bars

Plates XLIII to XLV.

Many so-called systems have been patented, especially in America, which are distinctive in nothing except in having some form of deformed bar for reinforcement in order to secure a mechanical bond. The efficiency of such bars is questioned by many prominent engineers, and tests have shown that they increase the strength for initial slippage very little, although they raise the ultimate bond stress considerably.

Plate XLIII shows types of bars commonly used in Europe. The Hyatt bar has been treated in Chapter IX, and the Kahn bar is shown also in Plate XIII.

Other forms of bars used to some extent in America are shown in Plate XLIV.

Most of these bars sacrifice section area for mechanical bond and are therefore inefficient. The Havemeyer Bars, shown in Plate XLV, Figure 1, overcome this difficulty in a very ingenuous manner.

Other much used bars are the twisted square Ransome bars, for which the patent has expired, and the round and square corrugated bars. The Kahn Rib Bar is very similar.

Only those shown in Plate XLV are much used commercially at present in this country. In design, tables giving the sectional area of the bars are necessary. The design is then the same as for plain bars, except that some engineers allow a 50 per cent increase in the bond stress specified.

XII Design of Ten Typical Floor Panels

Plates XLV to L

1. Procedure.

In order to present the advantages of different floor systems in reinforced concrete, panels were designed using each of ten systems which seemed to be typical of a class, under four different conditions of spans and loads, making forty separate designs. Quantities of material were computed for each design and prices taken from Gilletts "Cost Data" were applied, thus giving estimates of cost. While these prices vary in different parts of the country, the relative value for different material is approximately the same, so that the figures are fairly accurate for comparative values.

The panel was considered to be one in the center of the building, and the beam and girder support for the panel was considered in estimating its weight and cost. In each case a bending moment was assumed consistent with good engineering practice, and the unit stresses assumed are constant and conservative.

In systems using steel beams fireproofing was considered, except for the bottom flanges of the arch system. The ceiling was neglected in all designs. The unit price per square foot of floor includes the cost of the entire panel complete.

Plates XLVI to LV give the tabulated results for the designs with the conditions governing each. Plate LVI gives the computed values of weight of steel and concrete per square foot, dead load, and cost per square foot, to facilitate the comparison.

In order to observe the variation of cost with the span

and with the load, for the different systems, values of cost for varying spans and loads are plotted on graphs, in Plates LVII and LVIII. Similar graphs showing the variation of dead load with spans and with live loads are given in Plates LIX and LX. The two sets of graphs do not show the same variation, because systems using a great deal of steel are light but have a heavy cost on account of the much greater cost of steel. The dead loads are important in affecting the ultimate cost of the building, as a large dead load means an increase in the size of columns and foundations.

2. Results.

The two types at the bottom of the list as regards price are the flat slab and the Kahn Floredome; the former is at the bottom for heavy loads and the latter for light loads. The latter has much the advantage as regards dead load, however.

In general, a small slope on Plate LVII indicates a system advantageous for heavy loads, while a small slope on Plate LVIII indicates a system advantageous for long spans. Both the Vaughan sectional system and a one way tile system are inexpensive for short spans, but run up rapidly with increase in span.

The other systems run on an average. The sudden rise of the expanded metal systems is due to the fact that the use of this system with such a long span is inadvisable; the slab would be less expensive with a central beam.

The Hennebique runs the nearest to an average, but it has the highest dead load of any. The Kahn Floredome and tile systems

have the lightest dead loads. The sudden increase in the dead load of the one way tile with increase in span is due to the fact that the system is inapplicable to long spans. The Turner flat slab has medium weight, but saves in cost in the small amount of steel. The other systems, the Roebling, Two Way Tile, Flat Plate, and Arched Plate are average in both cost and weight. No great saving is made by the saving in centering with the last two, the cost being greatly increased on account of the relatively large amount of steel needed.

3. Conclusions

From the comparison of the floor systems in reinforced concrete, we should predict a much more extensive use of flat slab construction of any standard type. Not only is the flat slab inexpensive, but it possesses many other advantages in simplicity, lighting area, and appearance.

Systems of combination tile and also those using hollow metal boxes are advantageous in many respects, and may be expected to come into more general use.

Sectional systems will undoubtedly be used to a greater extent, especially as the development of the country reduces transportation charges and as labor charges increase.

The use of arches is apparently on the wane and they are seldom used except with a self-centering plate; but even then their advantage is doubtful.

Such standard systems as the Hennebique are thoroughly dependable and applicable to all spans and loads. Their great dead

load, however, tends to destroy their efficiency in tall buildings.

Of the systems employing special forms of reinforcement, such as a particular wire or metal plate, there seems to be little choice. None of them are especially efficient, and their partial success has been due more to advertisement than anything else.

Steel plates for centering do not result in the great saving that is usually claimed for them, besides being far from perfect as regards fireproofing of metal; hence a great success for them is hardly to be expected. Unit frames and deformed bars have their place in floor construction, but their importance is likely to be overrated.

Finally, every system will have its use under some particular case, even if it be rather limited; while wide commercial success will depend more on the type of company promoting the system and upon advertisement, than upon any minor intrinsic advantage. The greatest field for research and invention is with flat slab and combination tile or metal floors.



° AKME ° SYSTEM °
PLATE I




Fig. 1 | Plan




Fig. 2 | Section x-x

◦ AKME ◦ SYSTEM ◦
PLATE II




Fig. 1 Plan



Fig. 2 Section

◦ CANTILEVER ◦ FLAT ◦ SLAB ◦ SYSTEM ◦
PLATE III




Fig. 1 | Plan




Fig. 2 | Section x-x

• CORR-PLATE • SYSTEM •
PLATE IV




Fig. 1 Plan






Fig. 2 Section x-x

• SPIDER • WEB • SYSTEM •

PLATE V



THE UNIVERSITY OF CHICAGO



•TURNER•CANTILEVER•SYSTEM•

PLATE VI




Fig 1 Plan





Fig 2
Section Thru
Capital


• BERTINE • SYSTEM •

PLATE VII




Section

Fig 1



Section



Beam
Reinforcement

Fig. 2

W. 180 1801 180

18

18

18 18 18 18

18

18 18 18 18

• CHAUDY • SYSTEM •
PLATE VIII




Fig 1

Types of
Beam Reinforcement




Fig 2

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023	1024	1025	1026	1027	1028	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1472	1473	1474	1475	1476	1477	1478	1479	1480	1481	1482	1483	1484	1485	1486	14
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	----

° TYPES ° OF ° BEAM ° REINFORCEMENT ° PLATE IX




Fig 1
Coignet




Fig 2
Pavin De Lavarge





Fig. 3
Similar
Systems

°DE°VALLIERE°SYSTEM°
PLATE X




Fig 1




Fig 2

• GABRIEL SYSTEM •
PLATE XI




Fig. 1 Beam and Column



Fig. 2. Floor Slab

° HENNEBIQUE ° SYSTEM °
PLATE XII




Fig. 1




Fig. 2 Beam





Fig. 4 Column

•KAHN•SYSTEM•FLOREDOME•FLORETYLE•
PLATE XIII




Fig. 1 Floretyles




Fig. 2 Floredomes




Fig. 3 Kahn Bar

PLATE XIV



Scale $\frac{1}{8}'' = 1'-0''$

Fig. 1



Scale $1'' = 2'-0''$

Fig. 2

• CONCRETE • STEEL • CO. • SYSTEM • M •
PLATE XV




Fig 1 Section




Fig 2

Column
Connection






Fig 3 Plan

• WILSON • SYSTEM •
PLATE XVI



◦ COLUMBIAN ◦ SYSTEM ◦
PLATE XVII




Fig 1




Fig 3 Bars




Fig. 2





Fig. 4 Plan

Fig. 5
Beam Section

• MATRAI • SYSTEM •

PLATE XVIII




Fig. 1 Plan




Fig. 2 Section




Fig. 3 Girder Reinforcement

• METROPOLITAN • SYSTEM •
PLATE XIX




Fig 1 Section




Fig 2 Plan

° ROEBLING ° SYSTEM °

PLATE XX




Fig. 1. Ordinary Floor Slab




Fig. 2




Fig. 3

Methods of Attaching Reinforcement to Beam



Fig. 4



Fig. 5





Fig. 6 Arch Construction



• WHITE • • SYSTEM •
PLATE XXI




Fig. 1 Finished Floor




Fig 2 Section





Fig. 3 Plan

◦ GOLDING ◦ RIBBED ◦ FLOOR ◦ ARCH ◦

PLATE XXII



Expanded Metal
Reinforcement

° SYSTEMS ° WITH ° ARCHES ° ROLLED ° SECTIONS

PLATE XXIII






Fig 1



Flat Top


Fig 2

Monier Arch



Melan Arch

Fig 3



Wuench Arch

Fig 4

° SIEGWART · BEAM · SYSTEM ·

PLATE XXIV








Fig 1 Types
of Sections




Fig 2 Support




Fig 3 Plan

• UNIT • BILT • SYSTEM •
PLATE XXV




Fig 1 Section




Fig 2 Plan




Fig 3
Reinforcement
and Connections

° VAUGHAN ° SYSTEM °

PLATE XXVI




Fig 1 Floor Construction




Fig. 2 Single Beam

Fig. 3 Web Reinforcement





Fig 4 Plan




Fig 5 Complete Floor

• VISINTINI • SYSTEM •

PLATE XXVII




Fig. 1 Elevation and
Section of Beam
Warren Truss Type




Fig. 2
Fig. 3
Method of
tying to wall and
lifting beams






Fig. 4
Section of a Girder
Pratt Truss Type



Fig. 5
Stress Diagrams for Analysis



• CORR • TILE • FLOOR • SYSTEMS •
PLATE XXVIII




Fig 1 Section




Fig 2 Plan

• CORR • TILE • FLOOR • SYSTEMS •
PLATE XXIX




Fig. 1 System A




Fig. 2 System B




Fig. System C



12-34-18-004

I I I I

°FAWCETT° °SYSTEM°
PLATE XXX



Fig 1 Section between Beams




Fig 2 Section across Beams




Fig 3 Plan

•KAHN•SYSTEM•ONE•WAY•TILE•

PLATE XXXI

Fig 1 Section




Fig. 2 Plan





Fig 3 Cross Section

Fig. 4 Longitudinal
Section

• JOHNSON • SYSTEM •
 P L A T E X X X I I




Fig. 1 Type 1




Fig. 2 Type 2

◦ NOLAN ◦ TWO-WAY ◦ TILE ◦ SYSTEM ◦
PLATE XXXIII




Fig. 1 Section




Fig 2 Plan

SLABS CONSTRUCTED WITHOUT CENTERING

PLATE XXXIV




Fig. 1




Fig. 2




Fig. 3




Fig. 4



SLABS CONSTRUCTED WITHOUT CENTERING

PLATE XXXV




Fig 5




Fig 6




Fig 7




Fig 8




Fig 9

• SELF • SUPPORTING • • • METAL • FABRIC •

PLATE XXXVI




Fig 1 Rib Truss

Fig. 2 Multiplex
Steel
Plate





Fig. 3 Ferrolithic Plate




Fig 4 Self-Sentering




Fig 5 Hyrib




Fig 6

Corr - Mesh

Fig 7
Ferroinclave











Fig. 8

Usual
Shapes

• SLABS • WITH • FABRIC • REINFORCEMENT •
PLATE XXXVIII



• SLABS • WITH • FABRIC • REINFORCEMENT •
PLATE XXXIX




Fig. 7




Fig. 8




Fig. 9




Fig. 10

• TYPES OF MESH REINFORCEMENT •

PLATE XL




Fig 1 Hyatt




Fig 2 Donath




Fig 3 Muller





Fig 4 Chaudy



◦ FABRIC ◦ REINFORCEMENT ◦

PLATE XLI




Fig. 1 Expanded Metal
"Steelcrete"



Fig 2 Clinton Welded Wire





Fig 3



Cottancin Wire




Fig 4 Lockwoven
Fabric





Fig 5
Tie - Locked
Fabric

Fig 6



Triangular Mesh




Fig. 7 Rib Metal

• UNIT • FRAMES •
PLATE XLII



Fig 1

American System of
Reinforcement



Fig 2 Corrugated Bar Frame




Fig 3 Cummings Frame

THE HISTORY OF THE

• DEFORMED BARS •

PLATE XLIII




Fig. 1 Hyatt





Fig 2 Indented




Fig. 3 De Mann




Fig 4 Klett




Fig. 5 Kahn



Fig 6 Bonna





Fig. 7 Golding



Fig 8 Homan

◦ DEFORMED ◦ BARS ◦
P L A T E X L I V



Fig. 1 Corrugated Bar




Fig. 2 Lug Bar
General Fireproofing Co



Fig 3 Thatcher Bar
Concrete Steel Engineering Co



Fig. 4 Diamond Bar
Concrete Steel Engineering Co.

◦ DEFORMED ◦ BARS ◦ PLATE XLV





Fig. 1 Havemeyer - Round & Square



Bar With Lug



Fig 2 Twisted

Ransome Square



Round

Fig. 3 Corrugated

Square


Bars



Fig4 Rib Bar - Kahn

HENNEBIQUE SYSTEM

PLATE XLVI



Allowable stresses
steel 16000 #/sq in
concrete 500 #/sq in

Weight of concrete
150 #/cu. ft


Mixture 1 - 2 - 4 n = 15

TABLE OF QUANTITIES

Span in feet	16 x 16		24 x 24	
Live Load #/sq ft.	75	200	75	200
Thickness of Slab - In	4	5½	4	5½
Depth of Beams - In	22	28	29	34
Depth of girders - In	26	32	40	54
Wt of Slab #	12800	17650	28800	39700
Wt of beams #	5500	8600	24500	40400
Wt of Girders #	5900	9800	21600	29000
Wt of Panel #	24200	36050	74900	109100
Dead Load #/sq ft.	945	140	130	140
Wt of Steel in Slab #	184	254	430	587
Wt of Steel in Beams #	160	251	605	1041
Wt of Steel in Girders #	156	235	515	697
Wt Reinforcement #	500	740	1550	2325
Concrete - cu. ft.	161	240	500	730
Cost of Concrete	53.70	80.00	166.70	243.00
Cost of Steel	15.00	22.20	46.50	69.80
Cost of Forms - Etc	43.1	48.50	107.80	117.00
Total Cost	111.80	150.70	321.00	429.80
Cost per sq ft.	.44	.59	.56	.75

RIB TRUS SELF CENTERING PLATE

PLATE XLVII



Allowable stresses
steel 16000 #/sq in
concrete 500 #/sq in

Weight of concrete
150 #/cu ft

Mixture 1-2-4 n=15


$M = \frac{1}{12} w l^2$ in slabs and
 $\frac{1}{8} w l^2$ in beams and girders

TABLE OF QUANTITIES

Span in feet	16 x 16		24 x 24	
Live Load #/sq ft	75	200	75	200
Thickness of Slab in	5	5	5	5 1/2
Depth of Beams in	12 I 16	12 I 16	18 I 22	20 I 24
Depth of Girders in	15 I 19	20 I 24	24 I 28	24 I 28
Wt of Slab #	15850	15850	35700	39400
Wt of Beams #	3710	5510	14760	22000
Wt of Girders #	2750	3940	7920	9750
Wt of Panel #	22310	25300	58380	71150
Dead Load #/sq ft	87.5	99	101	123.5
Steel in Slab #	350	350	290	790
Steel in Beams #	1010	1510	3960	6100
Steel in Girders #	670	1040	1920	3850
Wt of Reinforcement #	350	350	790	790
Wt Structural Steel #	1680	2550	5880	9950
Concrete in Slab #	15850	15850	35700	39400
Concrete in Beams #	2700	4000	10800	15900
Concrete in Girders #	2080	2900	6000	6000
Total Concrete #	20630	22750	52500	61300
Cost of Concrete	45.70	50.50	116.50	136.00
Cost of Reinforcement	10.50	10.50	23.70	23.70
Cost of Structural Steel	50.40	76.50	176.00	298.00
Cost of Total Steel	60.90	87.00	199.70	321.70
Cost of Centering Etc	12.80	12.80	28.80	28.80
Cost per sq ft	.47	.60	.60	.84

VAUGHAN SYSTEM

PLATE XLVIII



Allowable stresses
steel 16000 #/sq. in.
concrete 500 #/sq. in.

Weight of concrete
150 #/cu. ft.

Mixture 1-2-4 $n=15$


$$M = \frac{1}{8} w l^2$$

TABLE OF QUANTITIES

Span in feet	16 X 16		24 X 24	
Live Load #/sq. ft.	75	200	75	200
Thickness of slab in	9	12	14	20
Depth of Beam in	15 I 19	20 I 24	20 I 24	24 I 28
Wt. of Slab #	15400	17900	46000	75000
Wt. of Beams #	2670	3040	7920	9620
Wt. of Panel #	18170	20940	53920	84620
Dead Load #/sq. ft.	71.0	82.0	93.5	147
Steel in Slab #	443	635	1550	2450
Steel in Beams #	670	1090	3120	5520
Total Steel #	1113	1675	4670	7970
Concrete Cu. Ft.	116	133	339	528
Cost of Concrete	38.70	44.30	112.50	176.00
Cost of Reinforcement	13.30	19.05	46.50	73.60
Cost of Structural Steel	20.10	31.20	93.60	165.40
Total Cost of Steel	33.40	50.25	140.10	239.00
Cost of Centering, etc	15.00	18.00	46.00	75.00
Total Cost	87.10	112.55	298.60	490.00
Cost per sq. ft.	.34	.44	.52	.85

EXPANDED - METAL - FLAT - SLAB

PLATE XLIX



Allowable stresses
 steel 16000 #/sq in
 concrete 500 #/sq in

Weight of concrete
 150 #/cu ft

Mixture 1-2-4 n=15


$M = \frac{1}{2} w l^2$ in slab and $\frac{1}{8} w l^2$
 in beams and girders

TABLE OF QUANTITIES

Span in feet		16 x 16		24 x 24	
Live Load #/sq ft		75	200	75	200
Thickness of Slab	in	4	6	4	6
Depth of Beams	in	12 I 16	15 I 19	15 I 19	24 I 28
Depth of Girders	in	15 I 19	20 I 24	24 I 28	24 I 28
Wt. of Slab	#	12 800	19 200	28 800	43 200
Wt. of Beams	#	4 210	5 500	10 220	22 750
Wt. of Girders	#	2 740	3 760	7 920	9 840
Wt. of Panel	#	19 750	28 460	46 940	75 700
Dead Load #/sq ft		770	111.0	815	131
Steel in Slab	#	190	238	428	540
Steel in Beams	#	1010	1340	3020	5750
Steel in Girders	#	670	1040	1920	3840
Wt. of Reinforcement		190	238	428	540
Wt. Structural Steel		1680	2380	4940	9590
Concrete in Slab	#	12 800	19 200	28 800	43 200
Concrete in Beams	#	3200	4 160	7 200	17 000
Concrete in Girders	#	2 070	2 720	6 000	6 000
Wt. Total Concrete	#	18 070	26800	42000	66 200
Cost of Concrete		40.00	59.30	93.00	146.30
Cost of Reinforcement		6.70	7.15	12.90	16.20
Cost Structural Steel		50.20	71.50	148.00	287.50
Cost Total Steel		56.90	78.65	160.90	303.70
Cost of Centering Etc		38.50	40.00	92.5	97.50
Cost per sq. ft.		.53	.69	.60	.95

CORR-TWO-WAY-TILE

PLATE L



Allowable stresses
steel 16000 #/sq. in.
concrete 500 #/sq. in.

Weight of concrete
150 #/cu. ft.

Mixture 1-2-4 $n=15$


$M = \frac{1}{2} w_l l^2$ for slab and
 $\frac{10}{64} w_l b l^2$ for beams

TABLE OF QUANTITIES

Span in feet	16 x 16		24 x 24	
Live Load #/sq. ft.	75	200	75	200
Thickness of Slab in	6	8	8 1/2	12
Depth of Beams in	12 I 16	18 I 22	20 I 24	20 I 24
Tile in Slab #	3330	3840	8700	9500
Tile in Beams #	640	960	1920	2880
Wt. of Tile #	3970	4800	10620	12380
Steel in Slab #	427	590	1610	1960
Steel in Beams #	10106	1760	3110	6250
Wt. of Steel #	1437	2350	4710	8210
Wt. of Concrete #	10750	13300	33500	40400
Wt. of Slab #	14080	17140	42200	49900
Wt. of Beams #	1650	2720	5030	9130
Wt. of Panel #	15730	19860	47230	59030
Dead Load #/sq. ft.	615	77.5	82.0	122.0
Cost of Concrete	23.80	29.50	74.20	89.50
Cost of Tile	48.70	48.70	11,200	112.00
Cost of Reinforcement	12.80	17.70	48.30	58.80
Cost of Structural Steel	31.40	52.90	93.50	187.50
Cost Total Steel	44.20	70.60	141.80	246.30
Cost of Centering Etc.	12.80	12.80	28.80	28.80
Cost per sq. ft.	.50	.71	.62	.82

TURNER - FLAT - SLAB

PLATE LI



Allowable stresses
 steel 16000 #/sq in
 concrete 500 #/sq in

Weight of concrete
 150 #/cu. ft.

Mixture 1-2-4 $n = 15$


$$M = \frac{1}{25} W l^2$$

TABLE OF QUANTITIES

Span in feet	16 x 16		24 x 24	
Live Load #/sq ft	75	200	75	200
Thickness of Slab - in	7	8	10	12
Wt. of Slab #/sq ft	85	100	120	145
Area of Steel sq in/sq ft	0.30	0.36	0.50	0.625
Wt of Steel #/sq ft	1.02	1.22	1.70	2.13
Total Steel #	262	313	980	1230
Dead Load #/sq ft	86	100	121	147
Cu Yds. Concrete	5.55	6.35	17.60	20.60
Extra Reinforcement #	107	107	308	308
Sq Ft. Centering	256	256	576	576
Cost of Concrete	50.00	57.20	158.50	186.00
Cost of Steel	7.86	9.40	29.40	36.90
Cost of Centering	28.20	28.20	63.50	63.50
Cost of Extra Steel	3.21	3.21	9.24	9.24
Total Cost	89.27	98.01	260.64	295.64
Cost per sq. ft.	0.348	0.383	0.453	0.514

KAHN FLOREDOME CONSTRUCTION

PLATE LII



Allowable stresses
 Steel 16000 #/sq in
 concrete 500 #/sq in

Weight of concrete
 150 #/cu. ft.

Mixture 1-2-4 n=15


$$M = \frac{1}{8} w l^2$$

TABLE OF QUANTITIES

Span in Feet	16 x 16		24 x 24	
Live Load #/sq ft	75	200	75	200
Thickness of Slab - In	6+2	8+2	8+2	10+2
Wt of Slab #/sq ft	50	60	60	61
Section of Beams - sq in	300	510	565	1150
Vol. Concrete in Slab - Cu Yds	3.16	3.78	8.54	10.10
Vol. Concrete in Beams - Cu Yds	1.27	1.92	3.5	7.1
Cu Yds Concrete	4.43	5.80	12.04	17.20
Wt Beams #/sq ft	20	23	25	51
Dead Load #/sq ft	70	83	85	122
Area of Steel in Slab $\frac{in^2}{sq ft}$.41	.79	.79	1.50
Area of Steel in Beams $\frac{in^2}{sq ft}$	1.5	2.5	2.81	5.75
Wt. of Steel in Slab #	356	686	1550	2940
Wt of Steel in Beams #	81.5	136	230	470
Total Steel #	437	822	1780	3410
Sq ft. Centering	64	64	144	144
Cost of Concrete	40.00	52.40	108.00	155.00
Cost of Steel	13.10	24.70	53.40	102.30
Cost of Centering	7.05	7.05	15.90	15.90
Cost of Domes & Hyrib	19.90	21.80	49.00	53.50
Total Cost	80.05	105.95	226.30	326.70
Cost per sq ft	.31	.41	.39	.57

KAHN ONE WAY TILE

PLATE LIII



Allowable stresses
steel 16000 #/sq in
concrete 500 #/sq in

Weight of concrete
150 #/cu ft.

Mixture 1-2-4 $n=15$


Plan, Panel 24 x 24 1.175" x 1" M = 16 W 12
Scale 3/8" = 1"
See Plate XXXI

TABLE OF QUANTITIES

Span in feet	16 x 16		24 x 24	
Live Load #/sq ft	75	200	75	200
Thickness of Slab - In	10-1	10-2	12-2	12-6
Wt of Slab #/sq ft	66	78	104	145
Section of Beams - Sq In	340	550	880	1300
Vol. Concrete in Slab Cu Yds	2.66	3.4	10.35	16.6
Vol. Concrete in Beams - Cu Yds	1.4	2.3	5.5	8.0
Cu. Yds. Concrete	4.06	5.7	15.85	24.6
Wt Beams # per sq ft	22	36	37	59
Dead Load #/sq ft	88	114	141	204
Area Steel in Slab #/sq ft	41	79	79	141
Area Steel in Beams #/sq ft	1.7	2.75	4.40	6.50
Wt Steel in Slab #	269	516	1160	2080
Wt Steel in Beams #	92.5	150	360	530
Total Steel #	361.5	666	1520	2610
Sq Ft Centering	128	128	256	256
No. of Tile	192	192	360	360
Cost of Concrete	36.60	51.40	143.00	222.00
Cost of Steel	10.80	20.00	45.60	78.40
Cost of Centering	14.10	14.10	28.20	28.20
Cost of Tile	48.00	48.00	110.00	110.00
Total Cost	109.50	133.50	326.80	438.60
Cost per sq ft	.43	.52	.57	.76

ARCH WITH SELF CENTERING PLATE

PLATE LIV



Allowable stresses
 steel 16000 #/sq. in.
 concrete 500 #/sq. in.

Weight of concrete
 150 #/cu. ft

Mixture 1-2-4 $n = 15$

Arch was taken from
 company's table.
 $M = \frac{1}{8} Wl^2$ in beams
 and girders

TABLE OF QUANTITIES

Span in feet	16 x 16		24 x 24	
Live Load #/sq. ft.	75	200	75	200
Thickness at Crown In	1	2	1	3
Average Wt. Slab #/sq. ft.	60	112	87	125
Size of Beams	4" I 21	15" I 42	12" I 31.5	18" I 55
Size of Girders	15" I 42	18" I 55	18" I 55	24" I 80
Wt. of Beams #	1000	2020	3020	5300
Wt. of Girders #	670	880	1320	1920
Total Wt. of Steel # (Structural)	1670	2900	4340	7220
Concrete - Cu. Yds	5.0	8.5	15.4	21.0
Wt. of Steel #/sq. ft.	6.5	8.5	7.4	12
Dead Load #/sq. ft.	66.5	120.5	94.4	137
Area of Plate sq. ft.	256	256	576	576
Wt. per sq. ft. of Plate #	1.5	1.5	1.5	1.5
Total Wt. Steel Centering	385	385	865	865
Cost of Concrete	45.00	76.50	138.80	189.00
Cost of Steel (Structural)	50.20	87.60	130.00	217.00
Cost of Steel Centering	11.60	11.60	26.00	26.00
Total Cost	106.80	175.10	294.80	432.00
Cost per sq. ft.	.42	.68	.51	.75

ROEBLING SYSTEM

PLATE LV



Allowable stresses
 steel 16000 #/P"
 concrete 500 #/P"

Weight of concrete
 150 #/cu ft.

Mixture 1-2-4 $n=15$

Plan Panel 24x24' 1.1.75 #/P
 Scale 3/8" = 1"
 See Plate XX

$M = \frac{1}{8} w l^2$

TABLE OF QUANTITIES

Span in feet	16 x 16		24 x 24	
Live Load #/sq ft.	75	200	75	200
Thickness of Slab - In.	5	7	5	7
Wt. of Slab #/sq ft.	60	85	60	85
Size of Beams	12 I 31.5	12 I 40	15 I 42	18 I 55
Size of Girders	15 I 42	18 I 55	20 I 65	2-20 I 65
Wt. of Beams #	1000	1280	3000	3950
Wt. of Girders #	670	880	1040	2080
Fireproofing - Cu yds.	1.04	1.2	2.67	2.96
Total Volume Concrete - Cu yds.	4.96	6.76	11.57	15.66
Wt. of Concrete #/sq ft.	79	104	81.8	110
Wt. of Steel #/sq ft.	6.5	8.9	7.2	10
Dead Load #/sq ft.	85.5	112.9	89	120
Wt. Steel per sq ft. Slab	.825	1.7	.825	1.7
Wt. of Reinforcement #	211	435	475	980
Sq ft Centering	336	344	780	792
Cost of Concrete	44.60	60.90	104.00	141.00
Cost of Reinforcement	6.32	13.10	14.25	29.40
Cost of Structural Steel	50.20	64.80	121.20	181.00
Cost of Centering	37.00	37.90	86.00	87.20
Total Cost	138.12	176.70	325.45	438.60
Cost per sq ft.	.54	.69	.56	.76

COMPARATIVE TABLE

PLATE LVI

S = wt. of steel per sq ft

C = wt. of concrete per sq. ft.


DL = dead load per sq. ft.

Cost = total cost per sq. ft.

		16 x 16								24 x 24							
		75				200				75				200			
		C	S	DL	Cost	C	S	DL	Cost	C	S	DL	Cost	C	S	DL	Cost
1. Turner	C	85				99				119				195			
	S		1				12				17				21		
	DL			86				100				121				147	
	Cost				35				38				45				51
2. Hennebique	C	93				137				127				186			
	S		2				3				27				4		
	DL			95				140				130				140	
	Cost				49				59				56				75
3. Kahn	C	68				80				82				116			
	S		1.7				32				31				59		
	DL			70				83				85				122	
	Cost				31				41				39				57
4. Roebling	C	60				85				60				85			
	S		25				27				29				35		
	DL			85				112				89				120	
	Cost				54				69				57				76
5. Vaughan	C	67				76				85				133			
	S		43				65				81				138		
	DL			71				82				93				147	
	Cost				34				44				52				85
6. One Way Tile	C	42				54				80				117			
	S		14				29				26				45		
	DL			88				114				141				209	
	Cost				43				52				57				76
7. Two Way Tile	C	47				52				58				70			
	S		.6				1				.9				14		
	DL			61				77				82				122	
	Cost				50				71				62				82
8. Flat Plate	C	80				89				91				107			
	S		7				10				10				16		
	DL			87				99				101				123	
	Cost				47				60				60				89
9. Arched Plate	C	58				108				85				123			
	S		8				12				9				14		
	DL			66				120				94				137	
	Cost				42				68				51				75
10. Expanded Metal	C	72				105				73				115			
	S		5				6				8				16		
	DL			77				111				81				131	
	Cost				53				69				60				95

VARIATION OF COST WITH LOAD

PLATE LVII



VARIATION OF COST WITH SPAN PLATE LVIII




VARIATION OF DEAD LOAD WITH LOAD

PLATE LIX



VARLATION OF DEAD LOAD WITH SPAN


PLATE LX







UNIVERSITY OF ILLINOIS-URBANA



3 0112 086829659